

PHYSICAL TESTING REPORT



0013

Earth4Earth Technology Ltd
85 Great Portland Street
London
W1W 7LT

FAO: Ms. Yan Geng

Report of Tests on: Carbon Capture Brick N10

Your Reference: N10/14-1

Lucideon Reference: N253627 - 2

Date Reported: 30-Sep-2025

Order Number:

Proforma Invoice

Date Logged: 21-Aug-2025

Date(s) of Test(s):

26-Sep-2025 to 26-Sep-2025

Determination of Compressive Strength
BS EN 772-1: 2011 (By Surface Grinding) + A1 2015

	Brick Length	Brick Width	Load	Compressive Strength
No.	mm	mm	kN	N/mm ²
1	214.8	102.1	869	39.6
2	214.9	102.4	895	40.7
3	214.8	102.4	859	39.1
4	214.9	102.6	938	42.5
5	214.7	102.6	794	36.1
6	214.7	102.2	871	39.7
7	214.8	102.3	889	40.5
8	214.6	102.2	704	32.1
9	214.6	102.4	947	43.1
10	215.0	102.3	819	37.2
Mean	215.0	102.0	858.5	39.1

Sample Preparation Procedure: OP148

Name of organisation carrying out sampling: EARTH 4 EARTH

Method of Sampling: Not Supplied

Method of Conditioning: Dryer at 105 deg C

Method of Preparation: Surface Ground

Orientation of Loading: Bed Face

Coefficient of Variation: 8.3 %

Crushing Machine: 1000KN

Machine Number: 89033

Serial Number: COM001

The sample was deviating and as a result, the test result(s) may be invalid.

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation.

End of Test Report

Mr Kaleem Zar
Engineer

PHYSICAL TESTING REPORT



0013

Earth4Earth Technology Ltd
85 Great Portland Street
London
W1W 7LT

FAO: Ms. Yan Geng

Report of Tests on: Carbon Capture Brick N10

Your Reference: N10/14-1

Lucideon Reference: N253627 - 2

Date Reported: 30-Sep-2025

Order Number: Proforma Invoice

Date Logged: 21-Aug-2025

Date(s) of Test(s): 17-Sep-2025 to 18-Sep-2025

Determination of Net & Gross Dry Density of Masonry Units (Except for Natural Stone)

BS EN 772-13:2000

	Net Dry Density	Gross Dry Density
No.	kg/m ³	kg/m ³
1	1940	1930
2	1940	1920
3	1930	1910
4	1950	1940
5	1920	1910
6	1940	1930
7	1940	1930
8	1900	1890
9	1960	1950
10	1930	1920
Mean	1940	1920

Sample Preparation Procedure: OP148

Name of organisation carrying out sampling: EARTH 4 EARTH

Method of Sampling: Not Supplied

The sample was deviating and as a result, the test result(s) may be invalid.

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation.

End of Test Report

Mr Kaleem Zar
Engineer

PHYSICAL TESTING REPORT



0013

Earth4Earth Technology Ltd
85 Great Portland Street
London
W1W 7LT

FAO: Ms. Yan Geng

Report of Tests on: Carbon Capture Brick N10

Your Reference: N10/14-1

Lucideon Reference: N253627 - 2

Date Reported: 30-Sep-2025

Order Number: Proforma Invoice

Date Logged: 21-Aug-2025

Date(s) of Test(s): 12-Sep-2025 to 12-Sep-2025

Determination of Dimensions, Flatness and Plane Parallelism

BSEN 771-3: 2011 (BSEN 772-16: 2011, BSEN772-20: 2000)

	Length	Width	Height	Flatness	Parallelism
No.	mm	mm	mm	mm	mm
1	215.0	102.0	66.0	0.2	0.2
2	215.0	102.5	65.5	0.1	0.1
3	215.0	102.5	65.5	1.3	0.3
4	215.0	102.5	65.5	0.1	0.7
5	214.5	102.5	65.0	0.3	0.4
6	214.5	102.0	65.5	0.2	0.2
Mean	215.0	102.0	66.0	0.4	0.3

Sample Preparation Procedure: OP148

Name of organisation carrying out sampling: EARTH 4 EARTH

Method of Sampling: Not Supplied

Method of Measurement: Method B

Measuring Device: Digital Calipers

Precision of Measuring Device: 2 decimal places

The sample was deviating and as a result, the test result(s) may be invalid.

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation.

End of Test Report

Mr Kaleem Zar
Engineer

PHYSICAL TESTING REPORT



0013

Earth4Earth Technology Ltd
85 Great Portland Street
London
W1W 7LT

FAO: Ms. Yan Geng

Report of Tests on: Carbon Capture Brick N10

Your Reference: N10/14-1

Lucideon Reference: N253627 - 2

Date Reported: 30-Sep-2025

Order Number: Proforma Invoice

Date Logged: 21-Aug-2025

Date(s) of Test(s): 17-Sep-2025 to 17-Sep-2025

Determination of Initial Rate of Water Absorption

BS EN 772-11: 2011 (Clay masonry units)

No.	Initial Rate of Water Absorption kg/(m ² .min)
1	0.9
2	1.0
3	1.0
4	0.8
5	1.2
6	1.6
7	1.0
8	1.4
9	0.8
10	1.4
Mean	1.1

Sample Preparation Procedure: OP148

Name of organisation carrying out sampling: EARTH 4 EARTH

Method of Sampling: Not Supplied

The sample was deviating and as a result, the test result(s) may be invalid.

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation.

End of Test Report

Mr Kaleem Zar
Engineer